



Anziehvorschrift für Zylinderkopf		984.274 passend für / suitable for adaptable à / adaptable a Renault	 Das Original	
Tightening Instructions for Cylinder Head				
Instructions de serrage pour culasse				
Prescripciones de apriete para culatas				
Schraubenkopf / Head shape Tête de vis / Cabeza de tornillo		Anziehreihenfolge/Tightening sequence/Ordre de serrage/Orden de apriete		
 759.180 M 12 x 113				
Anziehen/ Tightening/ Serrage/ Apriete	* 30 Nm ➤ 80°±4° ● 3 min ☐ lösen/loosen desserrer/aflojar ➤ 25 Nm + 213°±7°			
Zeichenerklärung / Explanations / Explication / Explicacion				
✱	neue Zylinderkopf-schrauben verwenden	use new cylinder head bolts	utiliser des vis neuves	emplar tornillos nuevos
★	Warmlauf (80°C)	warm up time (80°C)	chauffage (80°C)	calentamiento (80°C)
☐	Schrauben einzeln lösen und wieder anziehen	loosen and tighten each bolt	deserrer et serrer vis par vis	aflojar y apretar tornillo a tornillo
●	Setzzeit	relaxation time	durée de tassement	tiempo de espera
➤	Drehwinkel	torque angle	angle de serrage	ángulo de giro
Motortyp / Engine type / Type de moteur / Tipo de motor				
Ø: 81 mm; ⌀: 1,85 mm; 3 Löcher/Holes/Trous				
Mot: F8Q 610, 620, 624, 640, 682, 706, 710, 714 722, 724, 730, 732, 742, 764, 774, 776				
1,9 Ltr. Diesel; 44-48 kW (60-65 PS)				
R19, Clio, Megane, Rapid				
ElringKlinger AG, Max-Eyth-Str.2 72581 Dettingen / Erms. Tel. 07123/724 601			*984.274*	